



An online tool for residential  
remodeling & repair estimates

[About](#) | [Help](#) | [Contact](#)

## FULL SCOPE

### Project: 2/1

---

---

#### UTILITIES

---

Power: On

Water: On

### ITEMIZED NOTES BY LOCATION

---

---

#### DRIVEWAY

---

Floor: Cement

Width: 12

Length: 30

Sq Ft: 360

#### PATIO

---

Floor: Cement

Width: 15

Length: 20

Sq Ft: 300

#### FOYER

---

Floor: Ceramic

Width: 8

Length: 8

Sq Ft: 64

In Ft (Perimeter): 32

Outlets/Switches: 4

Light Fixture: Ceiling Light

Smoke Detector Req'd: 1

## **LIVING ROOM**

---

Floor: Carpet

Width: 13

Length: 15

Height: 12

Sq Ft: 195

Sq Ft (Walls): 672

In Ft (Perimeter): 56

Ceilings > 8ft.: 1

Outlets/Switches: 5

Light Fixture: Ceiling Fan

Smoke Detector Req'd: 1

A/C Vent: 1

## **DINING ROOM**

---

Floor: Ceramic

Width: 12

Length: 12

Sq Ft: 144

In Ft (Perimeter): 48

## **KITCHEN**

---

Floor: Ceramic

Width: 12

Length: 10  
Sq Ft: 120  
In Ft (Perimeter): 44  
Cabinet Lower: 12  
Cabinet Upper: 18  
Counter Top: 12  
Counter Top Type: Granite  
Angle Stop: 4  
Sink: 1  
Faucet: 1  
Garbage Disposal: 1  
Bold Colors: 1  
Ceilings > 8ft.: 1  
Outlets/Switches: 2  
GFCI: 2  
Light Fixture: Fluorescent

## **HALL**

---

Floor: Ceramic  
Width: 3  
Length: 12  
Sq Ft: 36  
In Ft (Perimeter): 30  
Bold Colors: 1  
Outlets/Switches: 2  
Light Fixture: Ceiling Light  
Smoke Detector Req'd: 1

## **BATHROOM 1**

---

Floor: Ceramic  
Width: 5  
Length: 8

Sq Ft: 40

In Ft (Perimeter): 26

Cabinet Lower: 3

Counter Top: 3

Counter Top Type: Granite

Angle Stop: 3

Sink: 1

Faucet: 1

Toilet: 1

Shower Head: 1

## **BEDROOM 1**

---

Floor: Carpet

Width: 11

Length: 15

Sq Ft: 165

In Ft (Perimeter): 52

Bold Colors: 1

Crown Molding: 1

Outlets/Switches: 5

Light Fixture: Ceiling Fan

Smoke Detector Req'd: 1

## **BEDROOM 2**

---

Floor: Carpet

Width: 13

Length: 13

Sq Ft: 169

In Ft (Perimeter): 52

Bold Colors: 1

Crown Molding: 1

Outlets/Switches: 6

Light Fixture: Ceiling Fan

Smoke Detector Req'd: 1

Interior Door: Slab (flush)

## **ITEMIZED NOTES BY TRADE**

---

---

### **Carpentry**

---

Install approx. 12 In ft of New Lower Kitchen Cabinets

Install approx. 18 In ft of New Upper Kitchen Cabinets

Install approx. 36 sq ft of New Granite Countertop w/4in. Backsplash at Kitchen

Install approx. 3 In ft of New Lower Bathroom Cabinets at bath1(3),

Install approx. 9 sq ft of New Granite Countertop w/4in. Backsplash at bath1(9),

Install 1 New Slab (flush) Interior Door(s) at rm2,

### **Electrical**

---

Install 24 New Outlets/Switches at foyer(4), living(5), kitchen(2), hall(2), rm1(5), rm2(6),

Install 2 New GFCI Outlet(s) at kitchen(2),

Install 5 New Hard-Wired Smoke Detector(s) at foyer, living, hall, rm1, rm2,

Install 2 New Ceiling Light(s) at foyer, hall,

Install 3 New Ceiling Fan(s) at living, rm1, rm2,

Install 1 New 4ft. Fluorescent Light(s) at kitchen,

### **Flooring**

---

Install 660 sq. ft. of Cement at driveway (360), patio (300),

Install 90 sq. yds. of Carpet at living (35), rm1 (20), rm2 (35),

\* Carpet is based per square yard of 12 ft. rolls \*

Install 404 sq. ft. of Ceramic Tile at foyer (64), dining (144), kitchen (120), hall (36), bath1 (40),

Install 340 In. ft. of Baseboards at foyer (32), living (56), dining (48), kitchen (44), hall (30), bath1 (26), rm1 (52), rm2 (52),

### **HVAC**

---

Install 1 New HVAC Vent(s) at living,

## **Interior Paint**

---

Apply approx. 933 sq. ft. of 3-Tone Interior Paint (walls/ceilings/trim) at foyer (64), living (195), dining (144), kitchen (120), hall (36), bath1 (40), rm1 (165), rm2 (169),

Apply approx. 195 sq. ft. of Ceilings > 8 ft. at living (195),

Apply approx. 490 sq. ft. of Primer for Bold Colors at kitchen (120), hall (36), rm1 (165), rm2 (169),

Apply approx. 104 ln. ft. of additional Interior Paint for Crown Molding at rm1 (52), rm2 (52),

## **Plumbing**

---

Install 7 New Angle Stops at kitchen(4), bath1(3),

Install 2 New Sinks at kitchen, bath1,

Install 2 New Faucets at kitchen, bath1,

Install 1 New Toilet(s) at bath1,

Install 1 New Shower-Head(s) at bath1,

Install New 1/3HP Garbage Disposal at Kitchen

## **Walls & Ceilings**

---

Install approx. 672 sq. ft. of New Drywall (walls) at living (672),

Install approx. 195 sq. ft. of New Drywall (ceilings) at living (195),

[Help](#) | [Privacy](#) | [Contact](#)

© 2023 AMP Concepts Online Inc.